KADUR DIVISION.

Notification dated 16th January 1935.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kadur Division, up to 1-30 P.M. of 11th February 1935 for the work of improving the Travellers' Bungalow at Kadur. An approximate estimate of quantites is given below. These quantities are not guaranteed. The work should be completed by the end of April 1935.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chikmagalur between the hours of 11 A.M. to 5 P.M., on office working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.—

4. Each tender must be accompanied by a deposit of Rupees two hundred (Rs. 200) in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for the work of improving the First Class Travellers' Bungalow at Kadur." in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for Contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Abstract estimate for improving the First Class Travellers' Bungalow at Kadur (1934-35).

Sl. No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
1	Dismantling the existing roofing materials and stacking	Sqr.	0 8 0	32·64	16
2	Dismantling and removing the couple rafters and Verandah rafters, etc., ...	..	..	Lumpsum	50
3	Dismantling the brick masonry and removing the debris to a distance from the spot ..	C.ft.	0 0 6	1,262	39
4	Burnt Brick in mortar, new	,,	0 5 0	981	307
5	Cudapah bearing slabs 1″ thick	S.ft.	0 3 0	109	20
6	Providing and fixing Renco ventilators ..	,,	2 0 0	63	126
7	Burnt stone slabs 6″ thick dressed and fixed in mortar	,,	0 8 0	180	90
8	Providing and fixing rolled steel joists 12″×6″× 44 lbs. including Railway freight, hoisting and encasing with wire net and cement mortar, etc., complete	Cwt.	12 0 0	14·2	170

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
9	Ferro concrete slabs 6″ thick	C.ft.	1 8 0	1,152	1,728
10	Coating top of concrete with spray-max and setting the available flooring tiles in mortar with pastering, etc., complete	Sqr.	10 0 0	23·04	230
11	Cost of centring for roofing complete	,,	8 0 0	23·04	184
12	Burnt brick in mortar parapet $1\frac{1}{8}' \times 2'$ as per design including plastering, etc., complete ..	R.ft.	1 4 0	122	152
13	Do $1\frac{1}{8}' \times 1\frac{1}{2}'$ over verandah roof ..	,,	1 2 0	201	226
14	Burnt brick in mortar cornice 9″ thick including plastering, etc., complete	R.ft.	0 14 0	333	291
15	Chunnam plastering 1″ thick	Sqr.	4 0 0	17·25	69
16	Painting girders	..	Lumpsum	..	10
17	Down or rain water pipes of sheet iron painted thick inside and outside, well revetted at junctions with overlaps of $\frac{5}{8}$″ beyond revet heads with semi-circular collars for fixing in the walls, etc., complete, as per specification.	R.ft.	1 4 0	160	200
18	Clearing site and other unforeseen charges ..	..	Lumpsum	..	92
	Total ..	..	..	..	4,000

L. A. H. WINCKLER,
Executive Engineer.

MEDICAL DEPARTMENT

OFFICE OF THE RESIDENCY SURGEON, CIVIL AND MILITARY STATION, BANGALORE.

NOTICE.

Notice is hereby given that sealed tenders will be received on Monday the 28th January 1935 by the Residency Surgeon, Bangalore, for the supply by contract of all articles of diet, etc., required for the use of the Bowring, Lady Curzon, Gosha and Isolation Hospitals, Bangalore, during the period from 1st April 1935 to 31st March 1936.

Forms of Tender (which also contain the specifications and conditions on which tenders will be considered and contracts let) can be had at the Office of the Residency Surgeon, Bowring Civil Hospital, Bangalore, on any day except Sundays between 8 A.M. and 12 NOON.

Each tender must be accompanied by a deposit (in Government Promissory Notes or Bank Receipts) as earnest deposit money of the amount noted against each group. When several groups are tendered for, one Bank receipt for the total amount of earnest deposit money will be received. This earnest money will be returned to unsuccessful tenderers immediately and to the others as soon as they have lodged the security mentioned in Para 9 of the Tender Form. No cash will be received. In default of such deposit the tender will be rejected.

J. B. HANCE,
Lieut.-Col., I.M.S.,
Residency Surgeon, Bangalore.

MISCELLANEOUS DEPARTMENTS

OFFICE OF THE DIRECTOR OF AGRICULTURE IN (MYSORE), BANGALORE.

Notice No. Roc. 1577—*Sc.* 194 *of* 34-35, *dated 28th December* 1934.

Sealed tenders will be received in the office of the undersigned up to 12 noon on the 28th nuary 1935 for the transport of the spraying materials noted in the Schedule.

For further particulars, please see page 47, Part VI of the *Mysore Gazette* dated 10th January 1935.